GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification No. G. N. 3 of 16th September 1936.

Sealed tenders will be received in the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 12 noon on 5th October 1936, for the supply of the following :—

1.	Teakwood Planks	12″×1″×6 ft.	.. .. ..	150 Nos.
2.	Do	12″×¾″×6 ft.	.. .. ..	100 „
3.	Do	12″×½″×6 ft.	.. .. ..	50 „
4.	Do	6″×2″×8 ft.	.. .. ..	10 „

The firms offering the above should quote only for well-seasoned Mysore Teakwood planks free from all defects, such as knots, bends, cracks, white and sap wood, etc., and the terms of delivery required are *F.O.R., Mysore or at the Office of the Superintendent, Power and Lighting, Mysore.*

Supply will have to be effected completely within six weeks of receipt of order.

The covers containing the tender should be marked "Tender for the supply of teakwood planks to be opened at 12 noon on 5th October 1936."

Any further details the tenderers may require may be had on application to the Deputy Chief Electrical Engineer, Bangalore.

Notification No. G. N. 4, dated 16th September 1936.

Sealed tenders will be received in the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 12 noon, on 5th October 1936, for the supply of the following :—

1.	Expanded Metal 3″×½″ mesh and ¼″×⅛″ thick, in standard rolls of 12 ft. ×8 ft	100 rolls.
2.	Hinges Iron 2″	200 pairs.
3.	Screws, flat-head, iron, 1½″, No. 8 size, Nettlefolds	20 gross.

Tenderers should quote for delivery *f.o.r., Mysore.*

Supply of the above will have to be effected completely within two weeks of receipt of order.

The covers containing the tender should be marked "Tender for the supply of Expanded Metal, etc., to be opened at 12 noon on 5th October 1936."

Any further details the tenderers may require may be had on application to the Deputy Chief Electrical Engineer, Bangalore.

M. HAYATH,
For *Chief Electrical Engineer.*

Abstract Notification dated 11th September 1936.

Attention of Firms dealing in Surveying Materials is invited to *Gazette* Notification on page 1423 of Part VI, dated 10th September 1936, calling for quotations for two New Engineer's Dumpy Level 12″, the last date for receipt of tenders being 29th September 1936.

Abstract Notification dated 11th September 1936.

Attention of Firms dealing in Hardware Materials is invited to the *Gazette* Notification, dated 10th September 1936, on page 1423 of Part VI, calling for quotations for 500 Turn Buckles, galvanized, ⅝″ dia., 12″ long, the last date for receipt of quotations being 30th September 1936.

Abstract Notification dated 11th September 1936.

Attention of Firms dealing in Hardware Materials is invited to the *Gazette* Notification, dated 17th September 1936, on page 1490 of Part VI, calling for quotations for two Pulley Blocks, complete of 5 and 7½ tons capacity each, the last date for receipt of quotations being 8th October 1936.

Abstract Notification dated 12th September 1936.

ENQUIRY G. N. 2.

Attention is invited of Timber Merchants to *Gazette* Notification, under the above Enquiry Number, published in Part VI, on page 1490, dated 17th September 1936, calling for quotations for supply of Mathi and Yellow Teakwood of sizes, the last date for receipt of quotations being 9th October 1936, 12 noon.

M. HAYATH,
Deputy Chief Electrical Engineer.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, MYSORE.

Notification dated 12th September 1936.

Sealed tenders in triplicate will be received at the office of the Superintendent, Power and Lighting, Mysore. Tenders should be superscribed with the name of the work given below. The rates should be noted both in words and figures.

2. The plan may be obtained at the office of the undersigned at all working hours.

3. The tenders should be drawn in conformity with the specification furnished, failing which the tenders will be disqualified.

4. The undersigned reserves the right to reject the tender or tenders without assigning any reason therefor.

5. The successful tenderer will be required to deposit an earnest money of Rs. 35 and execute necessary agreement within three days from the date of receipt of intimation as to the acceptance of the tender failing which the tender will be disposed off otherwise.

6. The materials to be used on the work should be either best quality English or American manufacture and conform to the specification. The work should be executed strictly in accordance with the wiring rules of this department as well as the Institution of Elecrtical Engineers. Mention should also be made of the catalogue number of the material offered.

7. No separate item should be noted in the tenders such as masonry repairs—painting, etc., as these should be included with the items given.

8. The successful tenderer should carry out any changes that might be suggested during the progress of work with regards to the location of cutouts, etc., without any extra cost if the estimate is not materially effected by such a deviation.

9. *Name of Work.*—"Rewiring the Power Installation—Weaving Section—of Silk Factory, Manantody Road, Mysore."

10. Last date and time for receiving and opening the tenders is 3rd October 1936 not later than 3 P.M.

11. The time allowed for the completion of the work is three weeks from the date of acceptance of the tender, failing which a penalty of annas two for each day's delay over and above the stipulated time specified will be enforced.

Details of Work.

1.	Supplying and running mains in 1" Braised conduit with necessary bends, rectangular junction boxes, etc., using No. 8 B. & S. V.I.R., insulated wire, 2,500 Megohms grade and accessories	Ft.	350
2.	Do do in ¾" W.I. Pipe embeded in the floor, using No. 12 B. & S. V.I.R., insulated wire, 2,500 Meg. grade and accessories ..	,,	200
3.	Supplying, fixing and wiring varnished teakwood board, 12"×12"×1" with battan and rear board equipping it 3 S.P., 15 amp. iron clad cut-outs using No. 12 B. & S., 2,500 Meg. grade insulated wire and accessories	No.	20
4.	Wiring the motors and starting switches using No. 14 B. & S., 3 conductor "BX" flexible steel armoured wire	,,	24
5.	Supplying spare fuse-holders 15 amp., for 15 amp. Iron clad cut-out ...	,,	12
6.	Grounding the conduit, armouring of "BX" cable, switches, etc.	Lump sum	

A. C. MUNIRATNAM,
Superintendent.